



**Construction of new classroom block**

PROJECT TITLE	<b>Huish Episcopi Academy, Langport</b>
CLIENT	Amanda Eastwood, Huish Episcopi Academy
ARCHITECT	Daron Stockham, Mark Richmond Architects
QUANTITY SURVEYOR	Lance Povah, Mark Richmond Architects
STRUCTURAL ENGINEER	Andrew Phillips, Phillips Consulting Engineers
CONTRACT VALUE	£747,497
DURATION OF WORKS	34 weeks
COMPLETION	27th May 2014
PROCUREMENT METHOD	Open tender
CONTRACT NO.	1581

Works comprised construction of a two storey classroom block at Huish Episcopi Academy in Langport, Somerset. The building was constructed off strip foundations, with beam and block flooring on the ground floor. The superstructure comprises blockwork, with external brick work and rendering. Steelwork was installed

to the first floor and roof in the stair landing area. The first floor comprises precast concrete planks, with access via prefabricated concrete stairs. The roof is a timber construction with Sarnafil system. The windows, external doors and curtain walling are polyester powder coated aluminium.

The ground floor internal layout comprises 2 classrooms, boys and girls toilets and disabled toilet, plant room, lift and lift control room, server room and lobby and circulation areas. The first floor comprises three classrooms and lobby and circulation areas.